



MODEL 12LP

CONCRETE OUTPUT PER HOUR

157 CUYD

120 M3



This model is 100% mobile. 12cuyd of concrete per batch, two, three or six aggregate compartments. Full setup with self erecting system.



CONCRETE OUTPUT PER HOUR	157 CUYD / 120 M3
CONCRETE PER BATCH (CPMB)	12 CUYD / 9 M3
BATCH CYCLE	4 - 5 MIN
AGGREGATE BATCHER VOL.	22 CUYD / 17.5 M3
AGGREGATE STORAGE	70 CUYD / 53 M3
AGGREGATE COMPARTMENTS	3 - 6
CEMENT BATCHER	5.5 TON
CEMENT STORAGE	52 CUYD - 46 MT
TOTAL HORSE POWER	95.5 H.P.
AUTOMATIC BATCH CONTROL	READY FOR ANY BRAND
PLANT CERTIFICATION	CPMB

Travel Length: 63' - Travel Height: 14' - Travel Width: 12'

For more information please contact our sales department.



